

EXECUTIVE BILL OF QUANTITIES REPORT

Concrete | Steel Reinforcement | Masonry (CHB) Works

Untitled Project

Report Date	July 21, 2026
Prepared By	_____
Checked By	_____
Grand Total Direct Cost	PHP 114,397.13

This report is a formatted summary derived from the Back-Up Computation and Checklist BOQ Summary of the linked *takeoff_boq_schedule.xlsx* workbook. Quantities are computed using Max Fajardo's Simplified Construction Estimate methodology with automated dual cross-checking (Section 2.5-2.7 of the project's Technical Specifications).

1. Project Summary

Work Section	Line Items	Subtotal Amount
Concrete Works	4	PHP 71,233.20
Steel Reinforcement	4	PHP 23,040.15
Masonry Works	2	PHP 20,123.78
GRAND TOTAL PROJECT DIRECT COST	10	PHP 114,397.13

Quality Assurance Snapshot

8 independent dual cross-check computations were run across all takeoff elements (Volume vs. Linear-Meter for concrete, Area vs. Block-Course for masonry, and table-value vs. theoretical weight for reinforcement). **0** check(s) exceeded the approved 2% divergence threshold and are flagged for manual review -- see Section 6, "QA Cross-Check Warnings."

2. Concrete Works -- Back-Up Computation

Item Code	Description	Location	Drwg Ref	Qty	Unit	Unit Cost	Amount	Status
CON-1.1	Concrete Works - Isolated Footings (F-1, Class A)	Grid 1-A to 4-D	S-1 Sheet 1	4.05	cu.m.	5,640.00	22,842.00	OK
CON-1.2	Concrete Works - Columns (C-1, Class A)	Ground to 2nd Floor	S-1 Sheet 1	1.08	cu.m.	5,640.00	6,091.20	OK
CON-1.3	Concrete Works - Beams (GB-1, Class A)	2nd Floor Framing	S-1 Sheet 1	1.50	cu.m.	5,640.00	8,460.00	OK
CON-1.4	Concrete Works - Slabs (SL-1, Class A)	2nd Floor Slab	S-2 Sheet 2	6.00	cu.m.	5,640.00	33,840.00	OK
Section Subtotal							PHP 71,233.20	

4 line item(s) recorded for Concrete Works. Each row traces to its source drawing sheet ("Drwg Ref") and plan location, per Section 2.7/2.8 of the Technical Specifications.

3. Steel Reinforcement -- Back-Up Computation

Item Code	Description	Location	Drwg Ref	Qty	Unit	Unit Cost	Amount	Status
REB-2.1 6	Deformed Rebar Ø16mm (C-1)	Ground to 2nd Floor	S-1 Shee t 1	181.79	kg	57.00	10,362.03	OK
REB-2.0	#16 G.I. Tie Wire (C-1)	Ground to 2nd Floor	S-1 Shee t 1	2.73	kg	90.00	245.70	OK
REB-2.2 0	Deformed Rebar Ø20mm (GB-1)	2nd Floor Framing	S-1 Shee t 1	213.06	kg	57.00	12,144.42	OK
REB-2.0	#16 G.I. Tie Wire (GB-1)	2nd Floor Framing	S-1 Shee t 1	3.20	kg	90.00	288.00	OK
Section Subtotal							PHP 23,040.15	

4 line item(s) recorded for Steel Reinforcement. Each row traces to its source drawing sheet ("Drwg Ref") and plan location, per Section 2.7/2.8 of the Technical Specifications.

4. Masonry Works -- Back-Up Computation

Item Code	Description	Location	Drwg Ref	Qty	Unit	Unit Cost	Amount	Status
MAS-3.1	100mm CHB Wall (W-1; Class B mortar: 0.522 bag/m², 0.0435 m³ sand/m²)	Exterior Perimeter	A-1 Shee t 1	20.40	sq.m.	609.02	12,424.01	OK
MAS-3.3	16mm Cement Plaster (2 faces, W-1; Class B: 0.192 bag/m², 0.0160 m³ sand/m²)	Exterior Perimeter	A-1 Shee t 1	40.80	sq.m.	188.72	7,699.78	OK
Section Subtotal							PHP 20,123.78	

2 line item(s) recorded for Masonry Works. Each row traces to its source drawing sheet ("Drwg Ref") and plan location, per Section 2.7/2.8 of the Technical Specifications.

5. BOQ Checklist Summary

Rolled-up quantities by item code, matching the "Checklist BOQ Summary" sheet of the linked Excel workbook. The Amount column uses a blended unit cost derived from the underlying Back-Up Computation rows.

Item No.	Item Code	Description	Unit	Qty	Blended Unit Cost	Amount
2.1	CON-1.1	Concrete Works - Isolated Footings	cu.m.	4.05	5,640.00	22,842.00
2.2	CON-1.2	Concrete Works - Columns	cu.m.	1.08	5,640.00	6,091.20
2.3	REB-2.16	Deformed Rebar Ø16mm	kg	181.79	57.00	10,362.03
2.4	REB-2.0	#16 G.I. Tie Wire	kg	5.93	90.00	533.70
2.5	CON-1.3	Concrete Works - Beams	cu.m.	1.50	5,640.00	8,460.00
2.6	REB-2.20	Deformed Rebar Ø20mm	kg	213.06	57.00	12,144.42
2.7	CON-1.4	Concrete Works - Slabs	cu.m.	6.00	5,640.00	33,840.00
2.8	MAS-3.1	100mm CHB Wall	sq.m.	20.40	609.02	12,424.01
2.9	MAS-3.3	16mm Cement Plaster	sq.m.	40.80	188.72	7,699.78
Grand Total						PHP 114,397.13

6. Drawing Element Traceability Notes

Every Back-Up Computation line item traces back to an originating drawing sheet and plan location, per tech_spec.md Section 1.3 item 7 ("Traceability & Verification"). The index below groups line items by source drawing sheet so a reviewer can cross-reference the BOQ against the working drawings sheet-by-sheet.

Drawing Ref	Location / Element	Item Code(s)	Work Section
A-1 Sheet 1	Exterior Perimeter	MAS-3.1, MAS-3.3	Masonry Works
S-1 Sheet 1	Grid 1-A to 4-D	CON-1.1	Concrete Works
	Ground to 2nd Floor	CON-1.2, REB-2.0, REB-2.16	Concrete Works, Steel Reinforcement
	2nd Floor Framing	CON-1.3, REB-2.0, REB-2.20	Concrete Works, Steel Reinforcement
S-2 Sheet 2	2nd Floor Slab	CON-1.4	Concrete Works

QA Cross-Check Warnings

No dual cross-check exceeded the approved 2% divergence threshold. All element quantities are confirmed by two independent derivation methods.