

EXECUTIVE BILL OF QUANTITIES REPORT

Concrete | Steel Reinforcement | Masonry (CHB) Works

Untitled Project

Report Date	July 22, 2026
Prepared By	_____
Checked By	_____
Grand Total Direct Cost	PHP 131,324.29

This report is a formatted summary derived from the Back-Up Computation and Checklist BOQ Summary of the linked *takeoff_boq_schedule.xlsx* workbook. Quantities are computed using Max Fajardo's Simplified Construction Estimate methodology with automated dual cross-checking (Section 2.5-2.7 of the project's Technical Specifications).

1. Project Summary

Work Section	Line Items	Subtotal Amount
Concrete Works	4	PHP 55,940.80
Steel Reinforcement	10	PHP 54,212.53
Masonry Works	2	PHP 21,170.96
GRAND TOTAL PROJECT DIRECT COST	16	PHP 131,324.29

Quality Assurance Snapshot

12 independent dual cross-check computations were run across all takeoff elements (Volume vs. Linear-Meter for concrete, Area vs. Block-Course for masonry, and table-value vs. theoretical weight for reinforcement). **0** check(s) exceeded the approved 2% divergence threshold and are flagged for manual review -- see Section 6, "QA Cross-Check Warnings."

2. Concrete Works -- Back-Up Computation

Item Code	Description	Location	Drwg Ref	Qty	Unit	Unit Cost	Amount	Status
CON-1.1	Concrete Works - Isolated Footings (F-1, Class A)	Uploaded Drawing	Uplo aded Draw ing	4.05	cu.m.	4,952.70	20,058.46	OK
CON-1.2	Concrete Works - Columns (C-1, Class A)	Uploaded Drawing	Uplo aded Draw ing	1.47	cu.m.	4,952.70	7,280.48	OK
CON-1.3	Concrete Works - Beams (GB-1, Class A)	Uploaded Drawing	Uplo aded Draw ing	2.02	cu.m.	4,952.70	10,029.23	OK
CON-1.4	Concrete Works - Slabs (S-1, Class A)	Uploaded Drawing	Uplo aded Draw ing	3.75	cu.m.	4,952.70	18,572.64	OK
Section Subtotal							PHP 55,940.80	

4 line item(s) recorded for Concrete Works. Each row traces to its source drawing sheet ("Drwg Ref") and plan location, per Section 2.7/2.8 of the Technical Specifications.

3. Steel Reinforcement -- Back-Up Computation

Item Code	Description	Location	Drwg Ref	Qty	Unit	Unit Cost	Amount	Status
REB-2.1 6	Deformed Rebar Ø16mm (F-1)	Uploaded Drawing	Uplo aded Draw ing	107.30	kg	54.68	5,867.16	OK
REB-2.0	#16 G.I. Tie Wire (F-1)	Uploaded Drawing	Uplo aded Draw ing	1.61	kg	62.50	100.62	OK
REB-2.2 0	Deformed Rebar Ø20mm (C-1)	Uploaded Drawing	Uplo aded Draw ing	284.08	kg	54.68	15,533.49	OK
REB-2.1 0	Deformed Rebar Ø10mm (C-1)	Uploaded Drawing	Uplo aded Draw ing	57.75	kg	54.68	3,157.77	OK
REB-2.0	#16 G.I. Tie Wire (C-1)	Uploaded Drawing	Uplo aded Draw ing	5.13	kg	62.50	320.62	OK
REB-2.2 0	Deformed Rebar Ø20mm (GB-1)	Uploaded Drawing	Uplo aded Draw ing	307.76	kg	54.68	16,828.32	OK
REB-2.1 0	Deformed Rebar Ø10mm (GB-1)	Uploaded Drawing	Uplo aded Draw ing	80.21	kg	54.68	4,385.88	OK
REB-2.0	#16 G.I. Tie Wire (GB-1)	Uploaded Drawing	Uplo aded Draw ing	5.82	kg	62.50	363.75	OK
REB-2.1 2	Deformed Rebar Ø12mm (S-1)	Uploaded Drawing	Uplo aded Draw ing	137.64	kg	54.68	7,526.16	OK
REB-2.0	#16 G.I. Tie Wire (S-1)	Uploaded Drawing	Uplo aded Draw ing	2.06	kg	62.50	128.75	OK
Section Subtotal							PHP 54,212.53	

10 line item(s) recorded for Steel Reinforcement. Each row traces to its source drawing sheet ("Drwg Ref") and plan location, per Section 2.7/2.8 of the Technical Specifications.

4. Masonry Works -- Back-Up Computation

Item Code	Description	Location	Drwg Ref	Qty	Unit	Unit Cost	Amount	Status
MAS-3.2	150mm CHB Wall (W-1; Class B mortar: 1.010 bag/m ² , 0.0840 m ³ sand/m ²)	Uploaded Drawing	Uplo aded Draw ing	18.00	sq.m.	830.16	14,942.94	OK
MAS-3.3	16mm Cement Plaster (2 faces, W-1; Class B: 0.192 bag/m ² , 0.0160 m ³ sand/m ²)	Uploaded Drawing	Uplo aded Draw ing	36.00	sq.m.	173.00	6,228.02	OK
Section Subtotal							PHP 21,170.96	

2 line item(s) recorded for Masonry Works. Each row traces to its source drawing sheet ("Drwg Ref") and plan location, per Section 2.7/2.8 of the Technical Specifications.

5. BOQ Checklist Summary

Rolled-up quantities by item code, matching the "Checklist BOQ Summary" sheet of the linked Excel workbook. The Amount column uses a blended unit cost derived from the underlying Back-Up Computation rows.

Item No.	Item Code	Description	Unit	Qty	Blended Unit Cost	Amount
2.1	CON-1.1	Concrete Works - Isolated Footings	cu.m.	4.05	4,952.70	20,058.46
2.2	REB-2.16	Deformed Rebar Ø16mm	kg	107.30	54.68	5,867.16
2.3	REB-2.0	#16 G.I. Tie Wire	kg	14.62	62.50	913.75
2.4	CON-1.2	Concrete Works - Columns	cu.m.	1.47	4,952.70	7,280.48
2.5	REB-2.20	Deformed Rebar Ø20mm	kg	591.84	54.68	32,361.81
2.6	REB-2.10	Deformed Rebar Ø10mm	kg	137.96	54.68	7,543.65
2.7	CON-1.3	Concrete Works - Beams	cu.m.	2.02	4,964.96	10,029.23
2.8	CON-1.4	Concrete Works - Slabs	cu.m.	3.75	4,952.70	18,572.64
2.9	REB-2.12	Deformed Rebar Ø12mm	kg	137.64	54.68	7,526.16
2.10	MAS-3.2	150mm CHB Wall	sq.m.	18.00	830.16	14,942.94
2.11	MAS-3.3	16mm Cement Plaster	sq.m.	36.00	173.00	6,228.02
					Grand Total	PHP 131,324.29

6. Drawing Element Traceability Notes

Every Back-Up Computation line item traces back to an originating drawing sheet and plan location, per tech_spec.md Section 1.3 item 7 ("Traceability & Verification"). The index below groups line items by source drawing sheet so a reviewer can cross-reference the BOQ against the working drawings sheet-by-sheet.

Drawing Ref	Location / Element	Item Code(s)	Work Section
Uploaded Drawing	Uploaded Drawing	CON-1.1, CON-1.2, CON-1.3, CON-1.4, MAS-3.2, MAS-3.3, REB-2.0, REB-2.10, REB-2.12, REB-2.16, REB-2.20	Concrete Works, Masonry Works, Steel Reinforcement

QA Cross-Check Warnings

No dual cross-check exceeded the approved 2% divergence threshold. All element quantities are confirmed by two independent derivation methods.